



City of North Royalton

Mayor Robert A. Stefanik

Nick Cinquepalmi

Service Director

Service Department

440-582-3002

fax 440-582-3089

TO: Laura Haller, Legislative Director
FROM: Nick Cinquepalmi, Service Director
DATE: February 24, 2014
RE: State Purchase Truck

We are requesting legislation be drawn up for approval at next Council Meeting of March 4, 2014 for state purchase with the following information:

- **2015 International Single Axle Truck @ \$93,631.00**

Rush Truck Center
11775 Highway Drive
Cincinnati, OH 45241
440-241-6404
440-658-2010 Fax
ODOT Contract STS Schedule Number: 023-13

Concord Road Equipment Mfg., Inc. – Plow and Dump body (\$52,587.59)
348 Chester Street
Painesville, Ohio 44077
440-357-5344
440-357-1942 Fax
Ohio DAS Contract STS Schedule Number: 800116
Index Number: STS515

If there are any questions, please call. Thanks.

/acd

c: Mayor Robert Stefanik
Thomas A. Kelly, Law Director
Eric Dean, Finance Director
Council President
Council
File



CONCORD

Road Equipment Mfg., Inc.
348 Chester Street
Painesville, OH 44077

Phone: (440) 357-5344 Fax: (440) 357-1942

Quote 57960

Quote Valid for 90 Days

Terms: NET 20

Page 1 of 2

Submitted To:

NORTH ROYALTON, CITY OF
13834 RIDGE RD
NORTH ROYALTON, OH 44133

Date: 2/23/2014

End User: SERVICE DEPARTMENT

Attention: NICK CINQUEPALMI

Delivery: SEE BELOW DELIVERY NOTES

County: CUYAHOGA

Acct Mgr: JEFFERY S. WARFIELD

Phone: (440) 582-3002

Fax: (440) 236-5024

STATE OF OHIO STATE TERM SCHEDULE CONTRACT; SCHEDULE NUMBER: 800116; INDEX NUMBER: STS515

CONCORD MINUTEMAN SNOW AND ICE CONTROL EQUIPMENT PACKAGE TO BE INSTALLED ON CUSTOMER SUPPLIED NEW SINGLE AXLE CAB AND CHASSIS TO INCLUDE THE FOLLOWING:

- SEVERE DUTY DUMP BODY:

HEAVY DUTY 10 FOOT LONG, 6.48 TO 7.77 CUBIC YARD CAPACITY, STEEL DUMP BODY WITH 30 INCH HIGH 7 GAUGE A1011 65KPSI STEEL SIDES WITH FULLY BOXED TOP RAIL, DIRT SHEDDING LOWER RUB RAIL, FULL LENGTH INTEGRAL HORIZONTAL BRACE, AND FRONT AND REAR CORNER POSTS; 36 INCH HIGH 7 GAUGE A1011 65KPSI STEEL TAILGATE WITH SIX PANEL STYLE BRACING, HEAVY DUTY UPPER TAILGATE HARDWARE, MANUAL RELEASE LOWER TAILGATE LATCHING MECHANISM, 7 GAUGE A1011 65KPSI STEEL BULKHEAD; 10 INCH STRUCTURAL STEEL I-BEAM LONGITUDINALS; 84 INCH WIDE x 1/4 INCH THICK AR-400 ABRASION AND IMPACT RESISTANT STEEL FLOOR; NTEA CLASS 60 DOUBLE ACTING UNDERBODY HOIST RATED AT 20.1 TON DUMPING CAPACITY IN THIS CONFIGURATION; BODY SANDBLASTED TO REMOVE ALL MILL SCALE, PRIMED WITH CR 900 SERIES EPOXY PRIMER AND PAINTED ONE SINGLE STAGE PPG DEL FLEET BLUE TO MATCH CHASSIS CAB, UNDERSTRUCTURE AND FRAME MOUNTED COMPONENTS PRIMED AND PAINTED BLACK

- BODY AND CHASSIS RELATED ACCESSORIES:

BODY MOUNTED 1/2 SIZE 7 GAUGE A1011 65KPSI STEEL LOAD BEARING CAB SHIELD WITH RECESSES FOR FRONT/REAR FACING, AS WELL AS STREET AND CURB SIDE FACING WARNING LAMPS, BODY MOUNTED STAINLESS STEEL THREE STEP FOLD UP LADDER WITH TWO ADDITIONAL SIDE MOUNTED STEPS AND REQUIRED GRAB HANDLES; FULL LENGTH TARP TIE DOWN RAILS ON BOTH SIDES OF BODY; REAR MUDDFLAPS STAINLESS STEEL "FAST FLAP" MOUNTING HARDWARE INSTALLED, STEEL SHIELDS WITH 1/2 LAPS IN FRONT OF REAR TIRES; REAR FULL WIDTH X FULL HEIGHT 3/4" THICK STEEL PINTLE HOOK MOUNTING PLATE WITH OFF SET LASHING RINGS AND 20 TON CAPACITY RIGID PINTLE HOOK; REMOUNT OEM REAR STT LAMPS TO CHASSIS FRAME; CONSPICUITY REFLECTIVE TAPE SYSTEM ON BODY SIDES AND TAILGATE; SPRING LOADED CLAMP STYLE SHOVEL HOLDER; HARDWOOD SIDEBOARDS, ETC.

- CENTRAL HYDRAULIC SYSTEM:

FRONT ENGINE DRIVEN 4.33 CUBIC INCH DISPLACEMENT REXROTH LOAD SENSING AXIAL PISTON PUMP MOUNTED ON REMOVABLE PLASMA CUT PLATE; FIVE (5) SECTION M4-12 LOAD SENSING CONTROL VALVE WITH THREE (3) AIR ACTUATED SECTIONS TO OPERATE DOUBLE ACTING DUMP BODY HOIST, DOUBLE ACTING PLOW LIFT, AND DOUBLE ACTING PLOW POWER ANGLE FUNCTIONS AND TWO (2) ELECTRIC PROPORTIONAL SECTIONS TO OPERATE SINGLE ACTING SPREADER CONVEYOR, SINGLE ACTING SPREADER SPINNER, VALVE INSTALLED IN A STAINLESS STEEL COMBINATION VALVE ENCLOSURE AND 42 GALLON HYDRAULIC OIL RESERVOIR; IN CAB AIR LEVER CONTROLLERS FOR HOIST AND PLOW FUNCTIONS; BOSCH REXROTH CS-420RC IN CAB GROUND SPEED PROPORTIONAL TWO (2) FUNCTION ELECTRONIC SPREADER CONTROLLER; LOW OIL SHUT DOWN SYSTEM WITH HYDRAULIC PUMP MOUNTED SHUTDOWN CARTRIDGE VALVE, OIL LEVEL SENSOR, IN CAB INDICATOR LAMP, WARNING BUZZER, AND MOMENTARY OVERRIDE SWITCH; CHASSIS PLOW HITCH MOUNTED HYDRAULIC CROSS-OVER RELIEF VALVE TO PROTECT SNOW PLOW POWER ANGLING CYLINDERS; INTERMEDIATE CHASSIS MOUNTED STAINLESS STEEL HYDRAULIC TUBING WITH SHORT HOSES ON EACH END FOR ALL CONNECTIONS TO THE FRONT AND REAR OF THE CHASSIS; ALL REQUIRED HYDRAULIC HOSES, FITTINGS, STAINLESS STEEL QUICK COUPLERS, OIL, ETC, TO MAKE A COMPLETE SYSTEM

- ELECTRICAL SYSTEM:

IN CAB POWER DISTRIBUTION PANEL FOR ALL BODY RELATED ELECTRICAL CIRCUITRY; BODY UP INDICATOR SYSTEM WITH SEALED MICRO SWITCH TRIGGER AND OPERATOR WARNING LIGHT; AMBER LED WARNING LAMPS, RED LED STOP-TAIL-TURN, AND CLEAR LED BACKUP LIGHTS, REAR FACING, RECESSED INTO DUMP BODY REAR CORNER POSTS; WHELEN AMBER LED WARNING LIGHTS INSTALLED REAR, SIDE, AND FORWARD FACING RECESSED INTO STEEL LIGHT BOXES IN BODY CAB SHIELD; NITE-SABER II SNOW PLOW LIGHTS WITH INTEGRATED MARKER AND TURN LIGHTS HOOD MOUNTED ON STAINLESS STEEL BRACKETS; REAR MOUNTED "LED" SPREADER WORK LIGHT; BACK UP ALARM; 7-WAY RV STYLE BLADE TYPE TRAILER PLUG, IN CAB ELECTRIC TRAILER BRAKE CONTROLLER, ALL FMVSS REQUIRED LED LIGHTING; ALL REQUIRED WIRING, HARNESSSES, CONNECTORS, ETC, TO MAKE A COMPLETE SYSTEM

- SNOW PLOW AND HITCH:

HUSTING 34" CHASSIS MOUNTED FRONT SNOW PLOW HITCH WITH ROLLER ASSIST KIT; 3"X 12" INCH DOUBLE ACTING LIFT RAM; CHASSIS SPECIFIC MOUNTING WITH 5/8 INCH THICK STEEL REINFORCED PUSH PLATES; HEAVY DUTY FORMED CHANNEL PLOW HITCH MOUNTED BUMPERS; BONNELL MODEL HSP10SP42TZ11 HEAVY DUTY SNOW PLOW WITH 10 FOOT LONG X 42 INCH HIGH "C" STYLE MOLDBOARD; SAFETY ORANGE POLY MOLDBOARD, TORSION SPRING SAFETY TRIP EDGE MECHANISM, HYDRAULIC RAM REVERSE DRIVE FRAME WITH NITRATED POWER ANGLING RAMS AND 34" PLOW HALVE OF HUSTING QUICK HITCH; CARBIDE INSERTED PLOW BLADES WITH STEEL COVER CUTTING EDGE, FULL LENGTH RUBBER SNOW DEFLECTOR, AND 36 INCH MOLDBOARD MARKERS

-ADDITIONAL INCLUDED BASE PACKAGE OPTIONS;

QUOTE CONTINUED ON NEXT PAGE



CONCORD

Road Equipment Mfg., Inc.
348 Chester Street
Painesville, OH 44077

Phone: (440) 357-5344 Fax: (440) 357-1942

Quote 57960

Quote Valid for 90 Days

Terms: NET 20

Page 2 of 2

Submitted To:
NORTH ROYALTON, CITY OF
13834 RIDGE RD
NORTH ROYALTON, OH 44133

Date: 2/23/2014
End User: SERVICE DEPARTMENT
Attention: NICK CINQUEPALMI
Delivery: SEE BELOW DELIVERY NOTES
County: CUYAHOGA
Acct Mgr: JEFFERY S. WARFIELD

Phone: (440) 582-3002

Fax: (440) 236-5024

QUOTE CONTINUED FROM PREVIOUS PAGE

- AUTOMATIC LUBRICATION SYSTEM, CHASSIS AND EQUIPMENT-UP TO MAXIMUM OF 30 LUBE POINTS, GROENVELD
- ABOVE BASE PACKAGE DUMP BODY SIDES, FRONT BULKHEAD, AND TAILGATE MANUFACTURED FROM 3/16" THICK AR400 ABRASION/IMPACT REISTANT 200 KPSI STEEL ILO 7 GAUGE A1011 65KPSI STEEL

*ALL PER THE CITY OF NORTH ROYALTON SPECIFICATIONS

TOTAL LIST PRICE, INSTALLED, PER UNIT:	\$ 63,780.82
LESS 15% STS CONTRACT DISCOUNT OF:	\$-(9,567.12)
LESS ADDITIONAL 3% DISCOUNT OF	\$-(1,626.41)

TOTAL NET PRICE, INSTALLED, PER UNIT:	\$ 52,587.29

* PER OUR OHIO STS CONTRACT, AN ADDITIONAL 0.5% (ONE HALF PERCENT) DISCOUNT IS AVAILABLE FOR PAYMENT OF INVOICE WITHIN 20 DAYS

* SEE ATTACHED SALES BUILD DOCUMENTS FOR COMPLETE DETAILS OF EQUIPMENT, ACCESSORIES, AND COMPONENTS INCLUDED IN THIS PROPOSAL

* CHASSIS SHALL HAVE A USABLE CAB TO AXLE DIMENSION OF APPROXIMATELY 84-87 INCHES, A FRONT ENGINE DRIVEN PTO PROVISION, AND INTEGRAL FULL C FRONT FRAME RAILS THAT EXTEND UP TO OR BEYOND THE CHASSIS GRILL TO ALLOW FOR PROPER EQUIPMENT INSTALLATION

* WARRANTY: CONCORD MINUTEMAN EQUIPMENT PACKAGES INCLUDE A 100% PARTS AND LABOR WARRANTY FOR A PERIOD OF ONE (1) YEAR AFTER COMPLETION / DELIVERY ON ALL EQUIPMENT, COMPONENTS, AND ACCESSORIES; DUMP BODY HOIST INCLUDES A FIVE (5) YEAR MANUFACTURER WARRANTY, SEE ATTACHED DOCUMENTATION; HYDRAULIC HOSE ASSEMBLIES CARRY A THREE (3) YEARS PARTS ONLY WARRANTY; WARRANTIES DO NOT INCLUDE NORMALLY CONSIDERED WEAR AND MAINTENANCE ITEMS, ROUTINE ADJUSTMENTS, ABUSE AND/OR NEGLIGENCE, MIS-USE, IMPROPER OPERATION, LACK OF MAINTENANCE AND/OR TRAINING, AND CONSEQUENTIAL DAMAGES AS A RESULT THEREOF.

* PROJECTED DELIVERY PERIOD: AS OF THE PROPOSAL DATE INDICATED ABOVE, OUR CURRENT PROJECTED ESTIMATED DELIVERY PERIOD IS APPROXIMATELY 90 TO 150 DAYS AFTER RECEIPT OF YOUR AUTHORIZATION TO PROCEED AND RECEIPT OF CHASSIS(S), ESTIMATED PROJECTED DELIVERY PERIOD CAN BE LONGER OR SHORTER BASED ON RECEIPT DATE OF ACTUAL AUTHORIZATION TO PROCEED, ACTUAL ARRIVAL OF YOUR CHASSIS(S), CURRENT ORDER BACKLOGS AND LEAD-TIMES FROM SUPPLIERS AND VENDORS AT TIME THE ORDER IS ACTUALLY PLACED. THE DELIVERY SCHEDULE PER THE OHIO DEPARTMENT OF ADMINISTRATIVE SERVICES CONTRACT IS 60 TO 210 DAYS AFTER RECEIPT OF YOUR ORDER AND CHASSIS(S); CONCORD ROAD EQUIPMENT MFG., INC. IS NOT RESPONSIBLE FOR DELAYS THAT ARE BEYOND IT'S REASONABLE EFFORTS TO CONTROL INCLUDING BUT NOT LIMITED TO CUSTOMERS DELAYS IN PLACING TIMELY ORDERS, STRIKES AND OR LABOR DISPUTES AND/OR DELAYS FROM PRIMARY EQUIPMENT AND COMPONENT MANUFACTURES, DELAYS IN FREIGHT, ACTS OF GOD, ETC.

Authorized by _____
JEFFERY S. WARFIELD

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from the above specifications involving extra costs will be executed only upon written orders and will become an extra charge over and above the estimate. All agreements are contingent upon strikes, accidents, or delays beyond our control. Owner is to carry fire, tornado and other necessary insurance. Our workers are fully covered by Worker's Compensation.